

ENVIRONMENTAL  
CLEARANCE



Government of India  
Ministry of Environment, Forest and Climate Change  
(Issued by the State Environment Impact Assessment  
Authority(SEIAA), TAMIL NADU)

To,

The Managing Director  
STATE INDUSTRIES PROMOTION CORPORATION OF TAMILNADU  
LIMITED (SIPCOT)  
19-A,Rukmani Lakshmiipathy Road, Egmore,Chennai -600008

**Subject:** Grant of Environmental Clearance (EC) to the proposed Project Activity under the provision of EIA Notification 2006-regarding

Sir/Madam,

This is in reference to your application for Environmental Clearance (EC) in respect of project submitted to the SEIAA vide proposal number SIA/TN/INFRA2/423033/2023 dated 20 May 2023. The particulars of the environmental clearance granted to the project are as below.

- |  |  |
|--|--|
| 1. EC Identification No.                   | EC23B039TN171847   |
| 2. File No.                                | 9262   |
| 3. Project Type                            | New  |
| 4. Category                                | B  |
| 5. Project/Activity including Schedule No. | 8(b) Townships and Area Development projects.  |
| 6. Name of Project                         | Proposed Development of Industrial Park in Virudhunagar over an extent of 425.55 Ha. (1051.10 Acres) |
| 7. Name of Company/Organization            | STATE INDUSTRIES PROMOTION CORPORATION OF TAMILNADU LIMITED (SIPCOT)                                 |
| 8. Location of Project                     | TAMIL NADU   |
| 9. TOR Date                                | N/A  |

The project details along with terms and conditions are appended herewith from page no 2 onwards.

Date: 31/07/2023

(e-signed)  
Thiru.Deepak S.Bilgi  
Member Secretary  
SEIAA - (TAMIL NADU)

*Note: A valid environmental clearance shall be one that has EC identification number & E-Sign generated from PARIVESH.Please quote identification number in all future correspondence.*

*This is a computer generated cover page.*

PARIVESH

(Pro-Active and Responsive Facilitation by Interactive,  
and Virtuous Environmental Single-Window Hub)





THIRU.DEEPAK S.BILGI, I.F.S.,  
MEMBER SECRETARY

STATE LEVEL ENVIRONMENT IMPACT  
ASSESSMENT AUTHORITY – TAMIL NADU  
3rd Floor, Panagal Maaligai,  
No.1, Jeenis Road, Saidapet,  
Chennai-15.  
Phone No. 044-24359973  
Fax No. 044-24359975

**ENVIRONMENTAL CLEARANCE (EC)**

**Letter No. SEIAA-TN/F.No.9262/2023 EC/8(a)/951/2023 dated:11.07.2023**

To

M/s. State Industries promotion Corporation of Tamil Nadu  
E.Kumaralingapuram, E.Muthulingapuram and Thulukkapatti  
Sattur and Virudhunagar taluk  
Virudhunagar District.

**Respected Sir,**

Sub: SEIAA, TN- Environmental Clearance – Proposed Development of Industrial Park in an area of 425.55 ha (1051.10 Acres) at E.Kumaralingapuram Village SF.Nos.134/1, 134/2, 134/3, 134/4, 134/5, 154/1, 154/2, 154/4A, 154/3, 154/4B, 155/1, 155/2, 155/3, 155/4, 155/5, 155/6, 155/7, 156/1, 156/2, 156/3, 156/4, 156/5, 156/6, 156/7, 156/8, 219/1, 219/2, 219/3, 220/1, 220/2, 220/3, 228/1, 228/2, 215/1A, 215/1B, 215/2, 215/3, 216, 217, 234/1, 234/4, 234/2, 234/3, 235/1, 235/2, 235/3, 235/4, 235/5A, 235/5B, 231/1, 231/2, 231/3, 231/4, 231/5, 231/6, 232/1, 232/5, 232/2, 232/3, 232/4, 232/6A, 232/6B1, 232/6B2, 229/1, 229/2, 229/3, 229/4, 226/6A, 227/1, 227/2, 227/3, 227/4, 227/5, 222/1, 222/2A, 222/2B1, 223, 224, 225/1, 225/2A, 225/3, 225/4, 225/5, 225/6A1, 225/6B1A, 225/6B1B, 221/1, 221/2, 221/3, 230/1, 230/2, 230/3, 230/4, 230/5, 230/6, 230/7, 206, 207, 233/1, 233/2A, 233/2B, 233/2C, 233/2D, 233/2E, 233/2F, 233/3, 235/6, 236, 237, 238/1, 238/2, 238/3, 238/4, 239/1A, 239/1B, 239/2, 239/3, 239/4, 239/5, 240, 263/1, 263/2, 263/3, 263/4A1, 263/4A2, 263/4B, 263/5A1, 263/5A2, 263/5A3, 263/6A1, 263/6B1, 263/6C1, 263/7, 263/8A, 263/9A, 263/10A, 263/11, 263/12A, 264/1, 264/2, 264/3, 264/4, 264/5, 264/6, 264/7, 265/2, 265/3, 265/4, 265/5, 266/1, 266/2, 266/3, 266/4, 266/5, 266/6, 266/8,

**MEMBER SECRETARY  
SEIAA-TN**

266/7, 266/9, 266/10, 266/11, 266/12, 266/13, 266/14, 266/15, 267/1, 267/2, 267/3, 267/4, 267/5, 268/1A, 268/1B, 268/1C, 268/1D, 268/2, 268/3, 268/4, 269/1, 269/2, 269/3, 269/4, 269/5, 269/6, 269/7, 270/1, 270/2, 270/3, 270/4, 270/5, 270/6, 270/7, 270/8, 271/1, 271/2, 271/3, 271/4A, 271/4B, 271/5, 271/6, 271/7, 271/8, 271/9, 271/10, 272/1, 272/2, 272/3, 272/4, 272/5, 272/6, 272/7, 272/8, 272/9, 273/1, 273/2, 273/3, 273/4, 273/5, 273/6, 273/7, 273/8, 273/9, 273/10, 274/1, 274/2A, 274/2B, 274/3, 274/4, 275/1, 275/2, 275/3, 276/1, 276/2, 276/3, 276/4, 276/5, 277/1, 277/2A, 277/2B, 277/3, 277/4, 278/1, 278/2A, 278/2B, 278/3, 278/4, 278/5, 279/1, 279/2, 279/3, 279/4, 279/5A, 279/5B, 279/6, 279/7, 279/8, 279/9, 280/1, 280/2A, 280/2B, 280/3, 280/4, 280/5, 280/6, 280/7, 280/8, 281/1, 281/2, 281/3, 281/4, 281/5A, 281/5B, 281/6, 281/7, 281/8, 281/9, 281/10, 282/1, 282/2A, 282/2B, 282/2C, 283/1, 283/2A1, 283/2C1, 283/3A, 283/4A, 283/5, 283/6A, 80/1, 80/2A, 80/2B, 81/1, 81/2, 81/3, 81/4, 81/5A, 81/5B, 81/6, 81/7, 82/1, 82/2, 82/3, 82/4, 82/5, 82/6, 82/7, 82/8, 82/9, 83/1, 83/2, 83/3, 83/4, 83/5, 83/6, 83/7A, 83/7B, 83/8, 84/1, 84/2, 84/3, 84/4, 84/5A, 84/5B, 84/6, 84/7, 85/1, 85/2, 85/3, 85/4, 86/2, 86/3, 86/4, 86/5, 86/6, 99/1A, 99/1B, 99/1C, 99/1D, 99/1E, 99/2A, 99/2B, 99/2C, 99/3, 99/4, 99/5, 99/6, 99/7, 100/1, 100/2, 101/1, 101/2, 101/3, 101/4, 101/5, 101/6A, 101/6B, 101/6C, 101/6D, 101/6E, 101/6F, 171, 172, 173/1, 173/2, 173/3, 173/4, 173/5, 173/6, 173/7, 173/8, 173/9, 174/1, 174/2, 174/3, 174/4, 174/5, 174/6, 174/7, 174/8, 175/1, 175/2, 175/3, 175/4, 175/5A, 175/5B, 175/6, 176/1, 176/2, 176/3A, 176/3B, 176/4, 177/1, 177/2, 177/3, 177/4, 177/5, 177/6, 177/7, 177/8, 177/9, 178/1, 178/2, 178/3, 178/4, 178/5A, 178/5B, 179/1, 179/2, 179/3A, 179/3B, 179/4, 179/5, 179/6, 202/1, 202/2A, 202/2B, 202/3, 202/4, 202/5A, 202/5B, 202/6A, 202/6B, 203/1, 203/2, 203/3A1, 203/3A2, 203/3B, 203/4, 204/1, 204/2, 204/3, 204/4, 205/1, 205/2, 205/3, 205/4, 205/5, 208/1, 208/2, 208/3, 208/4, 208/5, 208/6, 208/7, 209/1, 209/2, 209/3, 209/4, 209/5, 209/6, 210/1, 210/2A, 210/2B, 210/2C, 210/2D, 210/3, 210/4A1, 210/4A2, 210/4A3, 210/4A4, 210/4A5, 210/4B, 210/5, 211/1, 211/2, 211/3A, 211/3B, 211/4A, 211/4B, 211/4C, 211/4D, 211/5, 212/1A, 212/1B1, 212/1B2, 212/2A, 212/2B, 212/3, 212/4A, 212/4B, 212/5, 213/1, 213/2, 213/3A, 213/3B, 213/3C, 213/3D, 213/3E, 213/3F, 213/3G, 213/4, 213/5, 213/6, 180/1A, 180/1B, 180/1C, 180/1D, 180/2, 180/3, 181/1, 181/2, 181/3A, 181/3B, 181/4, 181/5, 181/6, 182/1, 182/2, 183/1A, 183/1B,

183/2, 184/1, 184/2, 184/3, 185/1, 185/2, 185/3, 185/4, 186/1, 186/2, 186/3, 187/1, 187/2, 187/3A, 187/3B, 187/3C, 187/4, 188/1, 188/2, 189/1, 189/2, 189/3, 189/4, 189/5, 189/6, 189/7, 190/1, 190/2, 190/3, 190/4, 191/1, 191/2, 191/3, 191/4, 191/5A, 191/5B, 191/6, 191/7, 192/1, 192/2, 192/3, 192/4A, 192/4B, 193/1, 193/2, 193/3, 193/4, 193/5, 193/6, 194/1, 194/2, 194/3, 195/1, 195/2, 195/3, 196/1A, 196/1B, 196/2, 196/3, 197/1, 197/2, 197/3, 197/4, 197/5A, 197/5B, 198/1, 198/2, 199/1, 199/2, 199/3, 199/4, 200, 201/1A, 201/1B, 201/2A, 201/2B, 201/3.

E.Muthulingapuram Village SF.Nos.14/1, 14/2, 14/3, 14/4, 14/5, 14/6, 14/7, 15/1, 15/2, 15/3, 62/1, 62/2, 62/3, 62/4, 63/1, 63/2, 63/3, 64, 67, 68/1, 68/2, 69/1, 69/2, 69/3, 69/4, 71/1, 71/2, 71/3, 71/4.

Thulukapatty Village SF.Nos.239/1, 239/2, 239/3, 239/4, 239/5, 239/6, 239/7, 239/8, 239/9, 239/10, 239/11, 240/1A, 240/1B, 240/2A, 240/2B, 240/2C, 240/3B, 240/3C, 240/3D, 240/4A, 240/4B, 240/4C, 240/4D, 240/6A, 240/6B, 240/7A, 240/7B, 240/8, 240/9A, 240/9B, 240/10A, 240/10B, 240/11, 240/12, 240/13, 241/1, 241/2, 241/3, 241/4A, 241/4B, 241/5, 241/6, 241/7, 241/8, 241/9, 242/1, 242/2, 242/3A, 242/3B, 242/4A, 242/4B, 242/5A, 242/5B, 242/5C, 242/6, 243/1A, 243/1B, 243/1C, 243/1D, 243/2, 243/3, 244, 245/1, 245/2, 247/1, 247/2, 247/3A, 247/3B, 247/4, 247/5, 248/1, 248/2, 248/3A, 248/3B, 248/4A, 248/4B, 248/4C, 248/5, 248/6, 248/7A, 248/7B, 248/8, 248/9, 248/10, 248/11, 250/1A, 250/1B, 250/2, 250/4, 250/5B, 250/6, 250/7A, 250/7B, 250/8A, 250/8B, 250/9, 250/10, 250/11, 250/12, 250/13, 250/14, 250/15, 250/16, 250/17 Sattur & Virudhunagar Taluks, Virudhunagar District Tamil Nadu By M/s. State Industries Promotion Corporation of Tamilnadu Limited (SIPCOT)- Issued - Regarding

- Ref:
1. TOR was issued vide Lr No. SEIAA-TN/F.No.9262/SEAC/8(b)/ToR-1205/2022 dated:14.07.2022.
  2. EIA report Submitted :23.03.2023
  3. Online Proposal No. SIA/TN/INFRA2/423033/2023, dated 22.03.2023
  4. Project proponent EC submitted dated: 22.03.2023.
  5. Minutes of the 377<sup>th</sup> SEAC meeting held on 10.05.2023.
  6. Minutes of the 624<sup>th</sup> authority meeting held on 31.05.2023
  7. Minutes of the 380<sup>th</sup> meeting of SEAC held on 17.05.2023.
  8. Minutes of the 627<sup>th</sup> SEIAA meeting held on 06.06.2023.

  
**MEMBER SECRETARY**  
**SEIAA-TN**

9. The project proponent reply furnished on 07.07.2023.

10. Minutes of the 637<sup>th</sup> Authority meeting held on 11.07.2023.

\*\*\*\*\*

This has reference to your application 4<sup>th</sup> & 5<sup>th</sup> cited, the proposal is for obtaining Environmental Clearance to Proposed Development of Industrial Park by M/s. State Industries Promotion Corporation of Tamilnadu Limited (SIPCOT) under Category B1 and Schedule S.No.8(b) Township and Area Development Projects under the Environment Impact Assessment Notification, 2006, as amended.

The Competent Authority and Authorized Signatory furnished the detailed information in Form 1, Form 1A and liquidate enclosures are as Annexures:

S.NO	Description	Details																																																																				
1	Name of the Project	State Industries Promotion Corporation of Tamil Nadu Limited (SIPCOT) Limited Tamil Nadu under SI.No.8(b) of the Schedule.																																																																				
2	Location	Latitude 9°25'26.91"N, Longitude 77°54'24.04"E (Centre Coordinates)																																																																				
3	Type of Project	Township and Area Development Projects Schedule 8(b):																																																																				
4	Total Plot Area	Breakup of Total Plot Area:																																																																				
	Area	<table border="1"><thead><tr><th>Description</th><th>Ha</th><th>Acres</th><th colspan="2">% of developable area</th></tr></thead><tbody><tr><td></td><td>258.96</td><td></td><td></td><td></td></tr><tr><td>Industrial Plot area</td><td>8</td><td>639.65</td><td></td><td>64.33%</td></tr><tr><td>Common amenities</td><td>8.069</td><td>19.93</td><td></td><td>2.00%</td></tr><tr><td>Commercial activities</td><td>12.101</td><td>29.89</td><td></td><td>3.00%</td></tr><tr><td>CETP &amp; Solid Waste Management</td><td>14.825</td><td>36.62</td><td></td><td>3.69%</td></tr><tr><td>Social Infrastructure</td><td>12.145</td><td>30.00</td><td></td><td>3.02%</td></tr><tr><td>Roads/ Storm water drain</td><td>33.101</td><td>81.76</td><td></td><td>8.22%</td></tr><tr><td>Green belt area</td><td>26.424</td><td>65.27</td><td></td><td>6.56%</td></tr><tr><td>OSR Area</td><td>36.947</td><td>91.26</td><td></td><td>9.18%</td></tr><tr><td><b>Developable area</b></td><td><b>402.58</b></td><td><b>0</b></td><td><b>994.38</b></td><td><b>100.00%</b></td></tr><tr><td>Water bodies</td><td>15.075</td><td>37.23</td><td></td><td></td></tr><tr><td>HT line &amp; ROW</td><td>4.090</td><td>10.09</td><td></td><td></td></tr></tbody></table>				Description	Ha	Acres	% of developable area			258.96				Industrial Plot area	8	639.65		64.33%	Common amenities	8.069	19.93		2.00%	Commercial activities	12.101	29.89		3.00%	CETP & Solid Waste Management	14.825	36.62		3.69%	Social Infrastructure	12.145	30.00		3.02%	Roads/ Storm water drain	33.101	81.76		8.22%	Green belt area	26.424	65.27		6.56%	OSR Area	36.947	91.26		9.18%	<b>Developable area</b>	<b>402.58</b>	<b>0</b>	<b>994.38</b>	<b>100.00%</b>	Water bodies	15.075	37.23			HT line & ROW	4.090	10.09		
Description	Ha	Acres	% of developable area																																																																			
	258.96																																																																					
Industrial Plot area	8	639.65		64.33%																																																																		
Common amenities	8.069	19.93		2.00%																																																																		
Commercial activities	12.101	29.89		3.00%																																																																		
CETP & Solid Waste Management	14.825	36.62		3.69%																																																																		
Social Infrastructure	12.145	30.00		3.02%																																																																		
Roads/ Storm water drain	33.101	81.76		8.22%																																																																		
Green belt area	26.424	65.27		6.56%																																																																		
OSR Area	36.947	91.26		9.18%																																																																		
<b>Developable area</b>	<b>402.58</b>	<b>0</b>	<b>994.38</b>	<b>100.00%</b>																																																																		
Water bodies	15.075	37.23																																																																				
HT line & ROW	4.090	10.09																																																																				

Vandipathai & Road	3.805	9.40	
	<b>425.55</b>	<b>1051.1</b>	
<b>Total</b>	<b>0</b>	<b>0</b>	

\*Individual Industries will be mandated to provide 33% of green belt in developable area of 402.580Ha

5	Brief Description of the project	<i>S.No</i>	<i>Type Industries</i>	<i>Plotted area in Acres</i>	<i>Plotted area in Ha</i>	<i>Approximate % of plotted area</i>
		1	Textile-wet processing unit	150.00	60.73	23.45
		2	Dry textiles (Apparel, Home Textiles) & Other Non - EC attracting industries.	489.65	198.24	76.55
		<i>Total</i>		<i>639.65</i>	<i>258.97</i>	<i>100</i>

Industrial Housing comprising of 7 nos. of towers with Stilt + 10 Floors and the total Built up Area for Industrial Housing is 1,11,858 sq.m & 1680 Dormitory Rooms.

**Detailed Built up Area break up**

Description	Area	Unit
Built up area per floor	1452.70	Sq.m
Total Number of floors in a Tower	Stilt + 10	Floors
Built up area of one Block	15979.70	Sq.m
Number of towers	7	Nos
<b>Total Built-up area – 7 Towers</b>	<b>1,11,858</b>	<b>Sq.m</b>

Description	Area	Unit
Number of Rooms Per Floor	24	Nos.
Total Number of Person in a floor	144	Nos.
Number of Persons per Room	6	Nos.
Carpet area per room - Dormitory	37.32	Sq.m

  
**MEMBER SECRETARY**  
**SEIAA-TN**  


		Carpet area per Person - Dormitory	6.22	Sq.m																																								
6	Project Cost	1800 Crores																																										
7	Water Requirement	<p>Total water requirement for the project is 29944 KLD. Fresh water requirement is 4545 (domestic purpose and Process), TTRO water 5000 KLD. Water requirement for Process and Utilities (887KLD) and green belt development (5210 KLD) and flushing (2656KLD) will be met from recycled water (20399 KLD).</p> <p>Fresh water (from Thamirabarani River) and TTRO Water will be sourced through TWAD.</p> <table border="1"> <thead> <tr> <th>Details</th> <th>Fresh water (KLD)</th> <th>TTRO (KLD)</th> <th>Recycled water (KLD)</th> <th>Total water (KLD)</th> </tr> </thead> <tbody> <tr> <td>Domestic (Industry)</td> <td>2758</td> <td></td> <td>0</td> <td>2758</td> </tr> <tr> <td>Domestic (Hostel)</td> <td>900</td> <td></td> <td>0</td> <td>900</td> </tr> <tr> <td>Flushing (Industry)</td> <td></td> <td>2183</td> <td>23</td> <td>2206</td> </tr> <tr> <td>Flushing (Hostel)</td> <td></td> <td>0</td> <td>450</td> <td>450</td> </tr> <tr> <td>Process &amp; Utilities</td> <td>887</td> <td>2817</td> <td>14716</td> <td>18420</td> </tr> <tr> <td>Green belt</td> <td></td> <td></td> <td>5210</td> <td>5210</td> </tr> <tr> <td><b>Total</b></td> <td><b>4545</b></td> <td><b>5000</b></td> <td><b>20399</b></td> <td><b>29944</b></td> </tr> </tbody> </table>			Details	Fresh water (KLD)	TTRO (KLD)	Recycled water (KLD)	Total water (KLD)	Domestic (Industry)	2758		0	2758	Domestic (Hostel)	900		0	900	Flushing (Industry)		2183	23	2206	Flushing (Hostel)		0	450	450	Process & Utilities	887	2817	14716	18420	Green belt			5210	5210	<b>Total</b>	<b>4545</b>	<b>5000</b>	<b>20399</b>	<b>29944</b>
Details	Fresh water (KLD)	TTRO (KLD)	Recycled water (KLD)	Total water (KLD)																																								
Domestic (Industry)	2758		0	2758																																								
Domestic (Hostel)	900		0	900																																								
Flushing (Industry)		2183	23	2206																																								
Flushing (Hostel)		0	450	450																																								
Process & Utilities	887	2817	14716	18420																																								
Green belt			5210	5210																																								
<b>Total</b>	<b>4545</b>	<b>5000</b>	<b>20399</b>	<b>29944</b>																																								
8	Wastewater Management	<table border="1"> <thead> <tr> <th>S.No</th> <th>wastewater</th> <th>Quantity (KLD)</th> <th>Method of Disposal</th> </tr> </thead> <tbody> <tr> <td colspan="4" style="text-align: center;"><b>Construction Phase</b></td> </tr> <tr> <td>1</td> <td>Sewage</td> <td>8</td> <td>Treated in 10 KLD Packaged STP</td> </tr> <tr> <td colspan="4" style="text-align: center;"><b>Operation Phase</b></td> </tr> <tr> <td>2</td> <td>Sewage from industries</td> <td>4468</td> <td>Will be treated by individual industries and treated sewage will be used for flushing and green belt development for IP</td> </tr> <tr> <td>3</td> <td>Sewage from Housing</td> <td>1215</td> <td>Will be treated in STP of 2000 KLD and treated sewage will be</td> </tr> </tbody> </table>			S.No	wastewater	Quantity (KLD)	Method of Disposal	<b>Construction Phase</b>				1	Sewage	8	Treated in 10 KLD Packaged STP	<b>Operation Phase</b>				2	Sewage from industries	4468	Will be treated by individual industries and treated sewage will be used for flushing and green belt development for IP	3	Sewage from Housing	1215	Will be treated in STP of 2000 KLD and treated sewage will be																
S.No	wastewater	Quantity (KLD)	Method of Disposal																																									
<b>Construction Phase</b>																																												
1	Sewage	8	Treated in 10 KLD Packaged STP																																									
<b>Operation Phase</b>																																												
2	Sewage from industries	4468	Will be treated by individual industries and treated sewage will be used for flushing and green belt development for IP																																									
3	Sewage from Housing	1215	Will be treated in STP of 2000 KLD and treated sewage will be																																									

				used for flushing for housing and green belt development for IP
		4	Effluent from individual industries	14736
				Will be treated in CETP of 3 Nos. X 5 MLD followed by ZLD system and treated effluent will be used for process & utilities.
9	Solid Waste Generation and Management		<b>Waste type</b>	<b>Quantity (kg/day)</b>
			<b>Disposal Method</b>	
			<b>Construction Phase</b>	
		1	Organic waste	41
		2	Inorganic waste	27
			<b>Total</b>	<b>68</b>
			<b>Operation Phase</b>	
		1	Organic waste	29781
		2	Inorganic waste	19854
			<b>Total</b>	<b>49635</b>
			<b>Industrial Housing</b>	
		1	Organic waste	2700
				Individual industries will segregate the waste and organic waste will be composted and used as manure for green belt development.
				Inorganic waste will be sold to TNPCB authorized recyclers/local vendors// Local body by individual industries.
				Organic wastes will be composted in Organic Waste Converter and the compost

  
**MEMBER SECRETARY**  
**SEIAA-TN**



					will be used as manure for green belt development.	
		2	Inorganic waste	1800	Inorganic waste will be collected and sold to TNPCB authorized recyclers / local vendors/ Local body by individual industries.	
		<b>Total</b>		<b>4500</b>		
10	Power Requirement	<b>Details</b>		<b>Capacity</b>		<b>Source</b>
		Power Requirement (MVA)		104		TANGEDCO
		Back-up (KVA)		2x1000 kVA DG by SIPCOT for industrial housing during power failure		DG
				Individual industries will have their own DG sets		DG
11	Man Power	Construction phase -150 nos. Operation phase – 1,20,300 (Including Industrial Housing)				
12	Green Belt Area	<b>S.No</b>	<b>Area details</b>	<b>Area (Ha)</b>	<b>Area (Acres)</b>	<b>% of developable area</b>
		1	OSR	36.947	91.26	9.18%
		2	Green belt	26.424	65.27	6.56%
		3	33% green belt in plot area to be allotted to individual industries	85.457	211.08	21.23%
			Total	148.828	367.61	36.97%
To plant 1500 Nos. of Trees/Hectare in 148.828 Ha and 560 Nos. of Compensatory trees to compensate the loss of 56 Nos. of trees to be cutoff.						

13	EMP Cost	S.No	<b>EMP activities</b>
		1.	Strom water drains, Culverts & rainwater harvesting pits
		2.	CETP with ZLD
		3.	Sewerage system & STP
		4.	Solid and Hazardous Waste Management
		5.	Solar lighting & Internal roads
		6.	Green belt development
		7.	Environmental Monitoring during construction phase
		8.	DG sets Acoustics and stack (for industrial Housing)
		9.	Rejuvenation of Pond
		10.	OCMS station at 4 locations
		11.	Baffle wall around the Match box industry
		12.	Conservation plan Schedule -1 Species
Capital Cost - 373.11 Crores			
Recurring cost - 644 Lakhs.			
Conservation plan for Peafowl – Rs.5.9 Lakhs shall be spent for Plantation of 100 Nos. of trees per year for five years in villages around the site, 5 Nos. of Water filling during summer, & Awareness programme in nearby schools regard to Peacock conservation.			
14	CER	Rs 50 Lakhs As per SEAC Meeting (5 lakhs per school Totally 50 Lakhs)	
15	Tor issued Letter	TOR was issued vide Lr No. SEIAA-TN/F.No.9262/SEAC/8(b)/ToR-1205/2022 dated:14.07.2022.	
16	EIA Received	EIA report Submitted :23.03.2023	

**Annexure 2- Affidavit**

I, Tmt. E. Sundaravalli I.A.S, Managing Director, Authorized Signatory, representing State Industries Promotion Corporation of Tamil Nadu Limited (SIPCOT) having registered office at 19-A, Rukmani Lakshmipathy Road, Egmore, Chennai – 600008, for proposed “Development of Industrial Park over an extent of 425.55 Hectares (1051.10 Acres) at E.Kumaralingapuram Village S.Nos. 134/1, 134/2, 134/3, 134/4, 134/5, 154/1, 154/2, 154/4A, 154/3, 154/4B, 155/1, 155/2, 155/3, 155/4, 155/5, 155/6, 155/7, 156/1, 156/2, 156/3, 156/4, 156/5, 156/6, 156/7, 156/8, 219/1, 219/2, 219/3, 220/1, 220/2, 220/3, 228/1, 228/2,

**MEMBER SECRETARY  
SEIAA-TN**


215/1A, 215/1B, 215/2, 215/3, 216, 217, 234/1, 234/4, 234/2, 234/3, 235/1, 235/2, 235/3, 235/4, 235/5A, 235/5B, 231/1, 231/2, 231/3, 231/4, 231/5, 231/6, 232/1, 232/5, 232/2, 232/3, 232/4, 232/6A, 232/6B1, 232/6B2, 229/1, 229/2, 229/3, 229/4, 226/6A, 227/1, 227/2, 227/3, 227/4, 227/5, 222/1, 222/2A, 222/2B1, 223, 224, 225/1, 225/2A, 225/3, 225/4, 225/5, 225/6A1, 225/6B1A, 225/6B1B, 221/1, 221/2, 221/3, 230/1, 230/2, 230/3, 230/4, 230/5, 230/6, 230/7, 206, 207, 233/1, 233/2A, 233/2B, 233/2C, 233/2D, 233/2E, 233/2F, 233/3, 235/6, 236, 237, 238/1, 238/2, 238/3, 238/4, 239/1A, 239/1B, 239/2, 239/3, 239/4, 239/5, 240, 263/1, 263/2, 263/3, 263/4A1, 263/4A2, 263/4B, 263/5A1, 263/5A2, 263/5A3, 263/6A1, 263/6B1, 263/6C1, 263/7, 263/8A, 263/9A, 263/10A, 263/11, 263/12A, 264/1, 264/2, 264/3, 264/4, 264/5, 264/6, 264/7, 265/2, 265/3, 265/4, 265/5, 266/1, 266/2, 266/3, 266/4, 266/5, 266/6, 266/8, 266/7, 266/9, 266/10, 266/11, 266/12, 266/13, 266/14, 266/15, 267/1, 267/2, 267/3, 267/4, 267/5, 268/1A, 268/1B, 268/1C, 268/1D, 268/2, 268/3, 268/4, 269/1, 269/2, 269/3, 269/4, 269/5, 269/6, 269/7, 270/1, 270/2, 270/3, 270/4, 270/5, 270/6, 270/7, 270/8, 271/1, 271/2, 271/3, 271/4A, 271/4B, 271/5, 271/6, 271/7, 271/8, 271/9, 271/10, 272/1, 272/2, 272/3, 272/4, 272/5, 272/6, 272/7, 272/8, 272/9, 273/1, 273/2, 273/3, 273/4, 273/5, 273/6, 273/7, 273/8, 273/9, 273/10, 274/1, 274/2A, 274/2B, 274/3, 274/4, 275/1, 275/2, 275/3, 276/1, 276/2, 276/3, 276/4, 276/5, 277/1, 277/2A, 277/2B, 277/3, 277/4, 278/1, 278/2A, 278/2B, 278/3, 278/4, 278/5, 279/1, 279/2, 279/3, 279/4, 279/5A, 279/5B, 279/6, 279/7, 279/8, 279/9, 280/1, 280/2A, 280/2B, 280/3, 280/4, 280/5, 280/6, 280/7, 280/8, 281/1, 281/2, 281/3, 281/4, 281/5A, 281/5B, 281/6, 281/7, 281/8, 281/9, 281/10, 282/1, 282/2A, 282/2B, 282/2C, 283/1, 283/2A1, 283/2C1, 283/3A, 283/4A, 283/5, 283/6A, 80/1, 80/2A, 80/2B, 81/1, 81/2, 81/3, 81/4, 81/5A, 81/5B, 81/6, 81/7, 82/1, 82/2, 82/3, 82/4, 82/5, 82/6, 82/7, 82/8, 82/9, 83/1, 83/2, 83/3, 83/4, 83/5, 83/6, 83/7A, 83/7B, 83/8, 84/1, 84/2, 84/3, 84/4, 84/5A, 84/5B, 84/6, 84/7, 85/1, 85/2, 85/3, 85/4, 86/2, 86/3, 86/4, 86/5, 86/6, 99/1A, 99/1B, 99/1C, 99/1D, 99/1E, 99/2A, 99/2B, 99/2C, 99/3, 99/4, 99/5, 99/6, 99/7, 100/1, 100/2, 101/1, 101/2, 101/3, 101/4, 101/5, 101/6A, 101/6B, 101/6C, 101/6D, 101/6E, 101/6F, 171, 172, 173/1, 173/2, 173/3, 173/4, 173/5, 173/6, 173/7, 173/8, 173/9, 174/1, 174/2, 174/3, 174/4, 174/5, 174/6, 174/7, 174/8, 175/1, 175/2, 175/3, 175/4, 175/5A, 175/5B, 175/6, 176/1, 176/2, 176/3A, 176/3B, 176/4, 177/1, 177/2, 177/3, 177/4, 177/5, 177/6, 177/7, 177/8, 177/9, 178/1, 178/2, 178/3, 178/4, 178/5A, 178/5B, 179/1, 179/2, 179/3A, 179/3B, 179/4, 179/5, 179/6, 202/1, 202/2A, 202/2B, 202/3, 202/4, 202/5A, 202/5B, 202/6A, 202/6B, 203/1, 203/2, 203/3A1, 203/3A2, 203/3B, 203/4, 204/1, 204/2, 204/3, 204/4, 205/1, 205/2, 205/3, 205/4, 205/5, 208/1, 208/2, 208/3, 208/4, 208/5, 208/6, 208/7, 209/1, 209/2, 209/3, 209/4, 209/5, 209/6, 210/1, 210/2A, 210/2B, 210/2C, 210/2D, 210/3, 210/4A1, 210/4A2, 210/4A3,

210/4A4, 210/4A5, 210/4B, 210/5, 211/1, 211/2, 211/3A, 211/3B, 211/4A, 211/4B, 211/4C, 211/4D, 211/5, 212/1A, 212/1B1, 212/1B2, 212/2A, 212/2B, 212/3, 212/4A, 212/4B, 212/5, 213/1, 213/2, 213/3A, 213/3B, 213/3C, 213/3D, 213/3E, 213/3F, 213/3G, 213/4, 213/5, 213/6, 180/1A, 180/1B, 180/1C, 180/1D, 180/2, 180/3, 181/1, 181/2, 181/3A, 181/3B, 181/4, 181/5, 181/6, 182/1, 182/2, 183/1A, 183/1B, 183/2, 184/1, 184/2, 184/3, 185/1, 185/2, 185/3, 185/4, 186/1, 186/2, 186/3, 187/1, 187/2, 187/3A, 187/3B, 187/3C, 187/4, 188/1, 188/2, 189/1, 189/2, 189/3, 189/4, 189/5, 189/6, 189/7, 190/1, 190/2, 190/3, 190/4, 191/1, 191/2, 191/3, 191/4, 191/5A, 191/5B, 191/6, 191/7, 192/1, 192/2, 192/3, 192/4A, 192/4B, 193/1, 193/2, 193/3, 193/4, 193/5, 193/6, 194/1, 194/2, 194/3, 195/1, 195/2, 195/3, 196/1A, 196/1B, 196/2, 196/3, 197/1, 197/2, 197/3, 197/4, 197/5A, 197/5B, 198/1, 198/2, 199/1, 199/2, 199/3, 199/4, 200, 201/1A, 201/1B, 201/2A, 201/2B, 201/3.

E.Muthulingapuram Village S.Nos. 14/1, 14/2, 14/3, 14/4, 14/5, 14/6, 14/7, 15/1, 15/2, 15/3, 62/1, 62/2, 62/3, 62/4, 63/1, 63/2, 63/3, 64, 67, 68/1, 68/2, 69/1, 69/2, 69/3, 69/4, 71/1, 71/2, 71/3, 71/4.

Thulukkapatti Village S.Nos. 239/1, 239/2, 239/3, 239/4, 239/5, 239/6, 239/7, 239/8, 239/9, 239/10, 239/11, 240/1A, 240/1B, 240/2A, 240/2B, 240/2C, 240/3B, 240/3C, 240/3D, 240/4A, 240/4B, 240/4C, 240/4D, 240/6A, 240/6B, 240/7A, 240/7B, 240/8, 240/9A, 240/9B, 240/10A, 240/10B, 240/11, 240/12, 240/13, 241/1, 241/2, 241/3, 241/4A, 241/4B, 241/5, 241/6, 241/7, 241/8, 241/9, 242/1, 242/2, 242/3A, 242/3B, 242/4A, 242/4B, 242/5A, 242/5B, 242/5C, 242/6, 243/1A, 243/1B, 243/1C, 243/1D, 243/2, 243/3, 244, 245/1, 245/2, 247/1, 247/2, 247/3A, 247/3B, 247/4, 247/5, 248/1, 248/2, 248/3A, 248/3B, 248/4A, 248/4B, 248/4C, 248/5, 248/6, 248/7A, 248/7B, 248/8, 248/9, 248/10, 248/11, 250/1A, 250/1B, 250/2, 250/4, 250/5B, 250/6, 250/7A, 250/7B, 250/8A, 250/8B, 250/9, 250/10, 250/11, 250/12, 250/13, 250/14, 250/15, 250/16, 250/17 of Sattur & Virudhunagar Taluk, Virudhunagar District, Tamil Nadu, hereby take oath and state as under in this affidavit:

- I. The total water requirement of the park is estimated at 29,944 KLD (Fresh water:4,545 KLD, TTRO water:5,000 KLD and Recycled water:20,399 KLD). Fresh water and TTRO water requirement for the Industrial Park is proposed to be sourced from TWAD Board.
- II. Power Supply (104 MVA) will be ensured from Tamil Nadu Generation and Distribution Co. Ltd. (TANGEDCO) Facility as a common supply system by SIPCOT to all member industries. Individual industries will have their own power back up.

  
**MEMBER SECRETARY**  
**SEIAA-TN**

- III. Storm water drainage will be provided as open concrete channels along the road ensuring proper collection of storm water and the same will be used for charging the rain water harvesting structures. We confirm that the storm water drain would not carry any untreated (or) treated sewage. All member industries will be instructed to provide rain water harvesting structures as per norms.
- IV. All member industries will be instructed to have their own solid waste and hazardous storage facility within their Plot. Inorganic waste will be sold to TNPCB authorized recyclers by member units. SIPCOT has earmarked 5 Acres of land for establishment of Solid Waste Management facility.
- V. All member industries will be mandated to store and dispose the hazardous waste generated within their premises as per Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016.
- VI. Individual industries will be mandated to provide STP with adequate capacity and maintain Zero Liquid Discharge (ZLD) system. Apart from this, CSTP of capacity 2000 KLD will be provided by SIPCOT for industrial housing facility and CETP of 15000 KLD (3X 5000 KLD in phase wise) will be provided by SIPCOT for treating effluent from wet textile industries.
- VII. Overall Greenbelt area of the park would be 148.828 Ha (i.e. 36.97% of developable area of 402.58 Ha).
- VIII. Tentative EMP cost of the park is INR 373.11 Crores. Details are given below:

S.No	Project Components	Capital Cost (INR Crores)
1	Storm Water drains, culverts & rainwater harvesting pits	68.2
2	CETP with ZLD	241.5
3	Sewerage system and STP	24.15
4	Solid and Hazardous waste Management	17
5	Solar lighting in internal road	12
6	Green belt development	3
7	Environmental Monitoring during Construction Phase	0
8	DG sets Acoustics and Stack (for Industrial Housing)	1.6
9	Rejuvenation of Pond	1.8
10	OCMS Station at Four location	2.4
11	Baffle wall around the Match box Industry	1.4

12	Conservation Plan Schedule-1 Species	0.059
<b>Total EMP Cost</b>		<b>373.11</b>

- IX. As per MoEF&CC Office Memorandum No. 22-65/2017-IA.III, dated 25.02.2021, SIPCOT will allocate INR 373.11 Crores towards Environment Management Plan (EMP) instead of allocation of funds under Corporate Environment Responsibility (CER). As per Minutes of 380th SEAC meeting, we commit to spend Rs.50 lakhs to 10 Nos. of nearby Government schools @ Rs. 5 lakhs each towards CER activities before obtaining CTO from TNPCB.

Declaration

I, Tmt. E. Sundaravalli, I.A.S., do hereby declare that the statement made by me under para (I) to (IX) are true and correct to the best of my knowledge and belief. Nothing is false and nothing is concealed in it.

**SEAC Recommendations:**

**Proposed Development of Industrial Park in an area of 425.55 ha (1051.10 Acres) at E.Kumaralingapuram Village SF.Nos.134/1, 134/2, 134/3, 134/4, 134/5, 154/1, 154/2, 154/4A, 154/3, 154/4B, 155/1, 155/2, 155/3, 155/4, 155/5, 155/6, 155/7, 156/1, 156/2, 156/3, 156/4, 156/5, 156/6, 156/7, 156/8, 219/1, 219/2, 219/3, 220/1, 220/2, 220/3, 228/1, 228/2, 215/1A, 215/1B, 215/2, 215/3, 216, 217, 234/1, 234/4,234/2, 234/3, 235/1, 235/2, 235/3, 235/4, 235/5A, 235/5B, 231/1, 231/2, 231/3, 231/4, 231/5, 231/6,232/1, 232/5, 232/2, 232/3, 232/4,232/6A, 232/6B1, 232/6B2, 229/1, 229/2, 229/3, 229/4, 226/6A, 227/1, 227/2, 227/3, 227/4, 227/5, 222/1, 222/2A, 222/2B1, 223,224, 225/1, 225/2A, 225/3, 225/4, 225/5, 225/6A1, 225/6B1A, 225/6B1B, 221/1, 221/2, 221/3, 230/1, 230/2, 230/3, 230/4, 230/5, 230/6, 230/7, 206, 207, 233/1, 233/2A, 233/2B, 233/2C, 233/2D, 233/2E, 233/2F, 233/3, 235/6,236, 237, 238/1, 238/2, 238/3, 238/4, 239/1A, 239/1B, 239/2, 239/3, 239/4, 239/5,240, 263/1, 263/2, 263/3, 263/4A1, 263/4A2, 263/4B, 263/5A1, 263/5A2, 263/5A3, 263/6A1, 263/6B1, 263/6C1, 263/7, 263/8A, 263/9A, 263/10A, 263/11, 263/12A,264/1, 264/2, 264/3, 264/4, 264/5, 264/6, 264/7, 265/2, 265/3, 265/4, 265/5, 266/1, 266/2, 266/3, 266/4, 266/5, 266/6, 266/8, 266/7, 266/9, 266/10, 266/11, 266/12, 266/13, 266/14, 266/15,267/1, 267/2, 267/3, 267/4, 267/5, 268/1A, 268/1B, 268/1C, 268/1D, 268/2, 268/3, 268/4,269/1, 269/2, 269/3, 269/4, 269/5, 269/6, 269/7, 270/1, 270/2, 270/3, 270/4, 270/5, 270/6, 270/7, 270/8,271/1, 271/2, 271/3, 271/4A, 271/4B, 271/5, 271/6, 271/7, 271/8, 271/9, 271/10,272/1, 272/2, 272/3, 272/4, 272/5, 272/6, 272/7, 272/8, 272/9, 273/1, 273/2, 273/3, 273/4, 273/5,**

  
**MEMBER SECRETARY**  
**SEIAA-TN**

273/6, 273/7, 273/8, 273/9, 273/10, 274/1, 274/2A, 274/2B, 274/3, 274/4, 275/1, 275/2, 275/3, 276/1, 276/2, 276/3, 276/4, 276/5, 277/1, 277/2A, 277/2B, 277/3, 277/4, 278/1, 278/2A, 278/2B, 278/3, 278/4, 278/5, 279/1, 279/2, 279/3, 279/4, 279/5A, 279/5B, 279/6, 279/7, 279/8, 279/9, 280/1, 280/2A, 280/2B, 280/3, 280/4, 280/5, 280/6, 280/7, 280/8, 281/1, 281/2, 281/3, 281/4, 281/5A, 281/5B, 281/6, 281/7, 281/8, 281/9, 281/10, 282/1, 282/2A, 282/2B, 282/2C, 283/1, 283/2A1, 283/2C1, 283/3A, 283/4A, 283/5, 283/6A, 80/1, 80/2A, 80/2B, 81/1, 81/2, 81/3, 81/4, 81/5A, 81/5B, 81/6, 81/7, 82/1, 82/2, 82/3, 82/4, 82/5, 82/6, 82/7, 82/8, 82/9, 83/1, 83/2, 83/3, 83/4, 83/5, 83/6, 83/7A, 83/7B, 83/8, 84/1, 84/2, 84/3, 84/4, 84/5A, 84/5B, 84/6, 84/7, 85/1, 85/2, 85/3, 85/4, 86/2, 86/3, 86/4, 86/5, 86/6, 99/1A, 99/1B, 99/1C, 99/1D, 99/1E, 99/2A, 99/2B, 99/2C, 99/3, 99/4, 99/5, 99/6, 99/7, 100/1, 100/2, 101/1, 101/2, 101/3, 101/4, 101/5, 101/6A, 101/6B, 101/6C, 101/6D, 101/6E, 101/6F, 171, 172, 173/1, 173/2, 173/3, 173/4, 173/5, 173/6, 173/7, 173/8, 173/9, 174/1, 174/2, 174/3, 174/4, 174/5, 174/6, 174/7, 174/8, 175/1, 175/2, 175/3, 175/4, 175/5A, 175/5B, 175/6, 176/1, 176/2, 176/3A, 176/3B, 176/4, 177/1, 177/2, 177/3, 177/4, 177/5, 177/6, 177/7, 177/8, 177/9, 178/1, 178/2, 178/3, 178/4, 178/5A, 178/5B, 179/1, 179/2, 179/3A, 179/3B, 179/4, 179/5, 179/6, 202/1, 202/2A, 202/2B, 202/3, 202/4, 202/5A, 202/5B, 202/6A, 202/6B, 203/1, 203/2, 203/3A1, 203/3A2, 203/3B, 203/4, 204/1, 204/2, 204/3, 204/4, 205/1, 205/2, 205/3, 205/4, 205/5, 208/1, 208/2, 208/3, 208/4, 208/5, 208/6, 208/7, 209/1, 209/2, 209/3, 209/4, 209/5, 209/6, 210/1, 210/2A, 210/2B, 210/2C, 210/2D, 210/3, 210/4A1, 210/4A2, 210/4A3, 210/4A4, 210/4A5, 210/4B, 210/5, 211/1, 211/2, 211/3A, 211/3B, 211/4A, 211/4B, 211/4C, 211/4D, 211/5, 212/1A, 212/1B1, 212/1B2, 212/2A, 212/2B, 212/3, 212/4A, 212/4B, 212/5, 213/1, 213/2, 213/3A, 213/3B, 213/3C, 213/3D, 213/3E, 213/3F, 213/3G, 213/4, 213/5, 213/6, 180/1A, 180/1B, 180/1C, 180/1D, 180/2, 180/3, 181/1, 181/2, 181/3A, 181/3B, 181/4, 181/5, 181/6, 182/1, 182/2, 183/1A, 183/1B, 183/2, 184/1, 184/2, 184/3, 185/1, 185/2, 185/3, 185/4, 186/1, 186/2, 186/3, 187/1, 187/2, 187/3A, 187/3B, 187/3C, 187/4, 188/1, 188/2, 189/1, 189/2, 189/3, 189/4, 189/5, 189/6, 189/7, 190/1, 190/2, 190/3, 190/4, 191/1, 191/2, 191/3, 191/4, 191/5A, 191/5B, 191/6, 191/7, 192/1, 192/2, 192/3, 192/4A, 192/4B, 193/1, 193/2, 193/3, 193/4, 193/5, 193/6, 194/1, 194/2, 194/3, 195/1, 195/2, 195/3, 196/1A, 196/1B, 196/2, 196/3, 197/1, 197/2, 197/3, 197/4, 197/5A, 197/5B, 198/1, 198/2, 199/1, 199/2, 199/3, 199/4, 200, 201/1A, 201/1B, 201/2A, 201/2B, 201/3.

E.Muthulingapuram Village SF.Nos. 14/1, 14/2, 14/3, 14/4, 14/5, 14/6, 14/7, 15/1, 15/2, 15/3, 62/1, 62/2, 62/3, 62/4, 63/1, 63/2, 63/3, 64, 67, 68/1, 68/2, 69/1, 69/2, 69/3, 69/4, 71/1, 71/2, 71/3, 71/4.

Thulukapatty Village SF.Nos. 239/1, 239/2, 239/3, 239/4, 239/5, 239/6, 239/7, 239/8, 239/9, 239/10, 239/11, 240/1A, 240/1B, 240/2A, 240/2B, 240/2C, 240/3B, 240/3C, 240/3D, 240/4A, 240/4B, 240/4C, 240/4D, 240/6A, 240/6B, 240/7A, 240/7B, 240/8, 240/9A, 240/9B, 240/10A, 240/10B, 240/11, 240/12, 240/13, 241/1, 241/2, 241/3, 241/4A, 241/4B, 241/5, 241/6, 241/7, 241/8, 241/9, 242/1, 242/2, 242/3A, 242/3B, 242/4A, 242/4B, 242/5A, 242/5B, 242/5C, 242/6, 243/1A, 243/1B, 243/1C, 243/1D, 243/2, 243/3, 244, 245/1, 245/2, 247/1, 247/2, 247/3A, 247/3B, 247/4, 247/5, 248/1, 248/2, 248/3A, 248/3B, 248/4A, 248/4B, 248/4C, 248/5, 248/6, 248/7A, 248/7B, 248/8, 248/9, 248/10, 248/11, 250/1A, 250/1B, 250/2, 250/4, 250/5B, 250/6, 250/7A, 250/7B, 250/8A, 250/8B, 250/9, 250/10, 250/11, 250/12, 250/13, 250/14, 250/15, 250/16, 250/17 Sattur & Virudhunagar Taluks, Virudhunagar District Tamil Nadu By M/s. State Industries Promotion Corporation of Tamilnadu Limited (SIPCOT) – For Environmental Clearance. (SIA/TN/INFRA2/423033/2023, dated 22.03.2023)

The details of the project furnished by the proponent are available in the website (parivesh.nic.in).


**The SEAC noted the following:**

1. The project/activity is covered under Category “B” of Item 8(b) “Township & Area Development Projects” of the Schedule to the EIA Notification, 2006.
2. TOR was issued vide Lr No. SEIAA-TN/F.No.9262/SEAC/8(b)/ToR-1205/2022 dated:14.07.2022.
3. EIA report Submitted :23.03.2023

The proposal was placed in 377<sup>th</sup> SEAC meeting held on 10.05.2023. Based on the presentation and documents furnished, SEAC decided to defer and directed the PP & the EIA Coordinator that PP shall revise the presentation and documents including the certain additional details so as to take up the proposal in the next ensuing authority meeting.

The proposal was again placed in 380<sup>th</sup> SEAC meeting held on 17.05.2023. Based on the presentation and documents furnished, SEAC decided to **recommend the proposal for the grant of Environmental Clearance**, subject to the standard conditions & normal conditions stipulated by MOEF &CC, in addition to the following specific conditions.

1. **The project proponent shall in-house only non - EIA attracting industries alone as committed especially Textile-wet processing unit & Dry textiles (Apparel, Home Textiles) & Other Non - EC attracting industries for the proposed SIPCOT plots as committed.**

  
**MEMBER SECRETARY**  
**SEIAA-TN**



2. **The project proponent shall obtain and maintain valid permission all time for supply of fresh water as committed.**
3. **The project proponent shall allot the plots under Court cases to entrepreneurs only after the final orders of the such Court cases.**
4. **The project proponent shall provide adequate capacity of Sewage treatment plant as committed for the proposed industrial housing and shall maintain & operate continuously to achieve the standards prescribed by the TNPCB/CPCB.**
5. **The project proponent shall ensure that non - EIA attracting Industries to be in-housed shall provide adequate individual STP and shall reuse the treated sewage for the toilet flushing & green belt/gardening.**
6. **The project proponent shall provide adequate capacity of CETP with ZLD for the proposed industrial activities as committed and shall maintain & operate continuously to achieve the standards prescribed by the TNPCB/CPCB.**
7. **The PP shall provide SCADA for operation and maintenance of CETP & STP as committed.**
8. **The project proponent shall ensure that industries in-housed shall operate and maintain the proposed STP/ETP efficiently and continuously to bring the quality of treated sewage/effluent to satisfy the discharge standards prescribed by the TNPCB at all times.**
9. **The project proponent shall ensure that non - EIA attracting Industries to be in-housed shall provide elevated STP of adequate capacity & its utilities above the ground level with adequate height considering highest rainfall & flood level /inundation point of view as recommended by the competent authority for the proposed project site.**
10. **The project proponent and the non - EIA attracting Industries to be in-housed shall provide & ensure that the utilities/ arrangements for fresh water supply, Storm/rain water management, and for reuse of treated sewage/effluent as proposed.**
11. **The project proponent shall ensure that the industries to be in-housed shall adhere that no treated or untreated trade effluent/sewage is discharged outside the premises under any circumstances.**
12. **The height of the stacks of DG sets shall be provided as per the CPCB norms.**
13. **The project proponent shall provide 4 Nos. CAQMS and Online Water quality analyzer for the CETP& STP for the parameters prescribed by the CPCB and shall hook up the same to CAC & WQW of TNPCB & CPCB portal for continuous & effective monitoring to achieve standards prescribed by the Board.**

14. The project proponent shall ensure that non - EIA attracting Industries to be in-housed shall provide adequate elevated closed area earmarked for collection, segregation, storage & disposal of wastes generated within the premises as per provisions of Solid Waste Management Rules, 2016, E-Waste (Management) Rules, 2016, Plastic Waste Management Rules, 2016 as amended, Bio-Medical Waste Management Rules, 2016 as amended, Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016 as amended, Construction and Demolition Waste Management Rules, 2016, & Batteries (Management and Handling) Rules, 2001.
15. **The proponent shall provide and maintain adequate green belt around the water bodies and to carryout periodic rejuvenation of water bodies within the proposed SIPCOT.**
16. **The project proponent shall periodically carryout conservation plan for Peafowl as committed for Plantation of 100 Nos. of trees per year for five years in villages around the site, 5 Nos. of Water filling during summer, & Awareness programme in nearby schools regard to Peacock conservation.**
17. **The PP shall plant 2500 Nos. of Trees/Hectare in 148.828 Ha of proposed green belt area excluding 560 Nos. of Compensatory trees to compensate the loss of 56 Nos. of trees to be cutoff.**
18. **The project proponent shall develop and maintain the project site without hindering the flow of the water bodies within the proposed SIPCOT area.**
19. The purpose of Green belt around the project is to capture the fugitive emissions, carbon sequestration and to attenuate the noise generated, in addition to improving the aesthetics. A wide range of indigenous plant species should be planted as given in the appendix in consultation with the DFO, State Agriculture University and local school/college authorities. The plant species with dense/moderate canopy of native origin should be chosen. Species of small/medium/tall trees alternating with shrubs should be planted in a mixed manner.
20. Taller/one year old Saplings raised in appropriate size of bags, preferably eco-friendly bags should be planted in proper espacement as per the advice of local forest authorities/botanist/Horticulturist with regard to site specific choices. The proponent shall earmark the greenbelt area with GPS coordinates all along the boundary of the project site with at least 3 meters wide and in between blocks in an organized manner.
21. The project proponent shall provide entry and exit points for the OSR area, as per the norms for the public usage and as committed.

  
**MEMBER SECRETARY**  
**SEIAA-TN**

22. The Proponent shall provide rain water harvesting sump of adequate capacity for collecting the runoff from rooftops, paved and unpaved roads as committed.
23. **The PP shall comply to all the EMP as committed before obtaining CTO from TNPCB.**
24. **The Proponent shall provide the dispenser for the disposal of Sanitary Napkins.**
25. **The project proponent shall provide a health care facility within the proposed SIPCOT as committed, possibly with a medical officer 24x7 in the project site for continuous monitoring the health of workers as committed.**
26. **The project proponent & the industries to be in-housed shall ensure buildings constructed are energy efficient and conform to the green building norms.**
27. **The project proponent shall insist the individual industries to provide and utilize at least 20% of roof top area for harnessing Solar Energy.**
28. **As accepted by the PP, the revised CER cost of Rs.50 Lakhs shall be spent for 10 Nos. of Government Schools each Rs. 5 Lakhs around the proposed SIPCOT towards the activities mentioned in the MoEF&CC OM Dated: 01.05.2018 before obtaining CTO from TNPCB.**

#### **SEIAA Recommendations**

The authority noted that the subject was appraised in 380<sup>th</sup> meeting of SEAC held on 17.05.2023. SEAC has furnished its recommendations for granting Environmental Clearance subject to the conditions stated therein. Subsequently, in the 627<sup>th</sup> authority meeting held on 06.06.2023, the authority decided to defer and decided the directs the PP to furnish certain additional particulars. In this connection, the project proponent has furnished reply vide Lr. Dt: 06.07.2023.

In this connection, the proposal was placed in the 637<sup>th</sup> Authority meeting held on 11.07.2023. The Authority after detailed discussions accepted the recommendation of SEAC and decided to grant of Environmental Clearance subject to the conditions as recommended by SEAC & normal condition in addition to the following conditions:

1. The project proponent shall in-house only non - EIA attracting industries alone as committed especially Textile-wet processing unit & Dry textiles (Apparel, Home Textiles) & Other Non - EC attracting industries for the proposed SIPCOT plots as committed.
2. The project proponent shall obtain and maintain valid permission all time for supply of fresh water as committed.

3. The project proponent shall ensure that non - EIA attracting Industries to be in-housed shall treat the effluent generated by providing adequate individual ZLD followed by reject management system and shall reuse the treated effluent for the process activity.
4. The project proponent shall ensure that non - EIA attracting Industries to be in-housed shall treat the Sewage generated by providing adequate individual STP and shall reuse the treated sewage for the toilet flushing & green belt/gardening as committed.
5. The project proponent shall provide adequate capacity of Sewage treatment plant as committed for the proposed industrial housing facility and shall maintain & operate continuously to achieve the standards prescribed by the TNPCB/CPCB.
6. The project proponent shall provide adequate capacity of CETP with ZLD for the proposed industrial activities as committed and shall maintain & operate continuously to achieve the standards prescribed by the TNPCB/CPCB.
7. The project proponent shall ensure that non - EIA attracting Industries & proposed industrial housing facility to be in-housed shall provide elevated STP& elevated CETP of adequate capacity & its utilities above the ground level with adequate height considering highest rainfall & flood level /inundation point of view as recommended by the competent authority for the proposed project site.
8. The project proponent shall ensure that non - EIA attracting Industries to be in-housed shall provide roof top solar panel to harness solar energy.
9. The project proponent shall ensure that proposed industrial housing facility and other buildings shall be energy efficient and confirming to IGBC standards.
10. The project proponent shall ensure that the industries to be in-housed shall ensure buildings constructed are energy efficient and conform to the green building norms.
11. The project proponent shall provide & maintain OWC of adequate capacity as committed for the proposed industrial housing facility.
12. The project proponent shall provide & maintain green fuel-based DG sets as committed.
13. The PP shall conduct periodic training to the industrial employees in regard to emergency evacuation plan.
14. The structural stability of STP & CETP provided shall be periodically certified by the reputed academic institute or concerned competent authority.
15. The proponent shall continuously adopt carbon neutral strategies to confirm carbon neutr environment.
16. The project proponent shall ensure that non - EIA attracting Industries to be in-housed shall provide adequate elevated closed area earmarked for collection, segregation,

  
**MEMBER SECRETARY**  
**SEIAA-TN**

storage & disposal of wastes generated within the premises as per provisions of Solid Waste Management Rules, 2016, E-Waste (Management) Rules, 2016, Plastic Waste Management Rules, 2016 as amended, Bio-Medical Waste Management Rules, 2016 as amended, Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016 as amended, Construction and Demolition Waste Management Rules, 2016, & Batteries (Management and Handling) Rules, 2001.

17. The project proponent shall ensure that the industries to be in-housed shall adhere that no treated or untreated trade effluent/sewage is discharged outside the premises under any circumstances.
18. The project proponent and the non - EIA attracting Industries to be in-housed shall provide & ensure that the utilities/ arrangements for fresh water supply, Storm/rain water management, and for reuse of treated sewage/effluent as proposed.
19. The project proponent shall provide & maintain adequate storm water management & rain water harvesting structures as committed for the project site.
20. The project proponent shall provide adequate arrangements for disposal of excess storm water and shall obtain necessary permission from the competent authority before obtaining CTO.
21. The project proponent shall ensure that industries to be in-housed shall operate and maintain the proposed STP / CETP efficiently and continuously to bring the quality of treated sewage/effluent to satisfy the discharge standards prescribed by the CPCB at all times.
22. The project proponent & the Industries to be in-housed shall periodically conduct and submit fire safety study, emergency evacuation plan, risk assessment study, occupational health safety study for the worst case scenario in regard to existing safety measures/standard operating procedures adopted for the process/ equipment/utilities for operation & maintenance and the storage areas of products, raw materials, solvent, fuel, etc. in the different operating zones of the plant at least once in a year to regularly identify safety fragile areas within the plant which requires regular monitoring and the proponent shall submit the same along with timeline for implementation of the said recommendations to the concerned departments.
23. The project proponent shall ensure Industries to be in-housed shall adhere to provide adequate parking space for visitors of all inmates including clean traffic plan as committed.

24. The project proponent shall adhere to the approval obtained for the source of fresh water supply from the competent Authority.
25. The project proponent & the industries to be in-housed shall strictly adhere to all biosafety standards, hygienic standards and safety norms of working staff and patients to be strictly from time to time as guidance of competent authority.
26. The project proponent & the industries to be in-housed shall strictly adhere to the disaster management and disaster mitigation measures/standards to avoid any calamities.
27. The project proponent & the industries to be in-housed shall strictly adhere to the EIA/EMP and disaster management plan.
28. The activities should in no way cause emission and build-up Green House Gases. All actions to be ecofriendly and support sustainable management of the natural resources within and outside the campus premises.
29. The project proponent should strictly comply with, Tamil Nadu Government order regarding ban on one time use and throwaway plastics irrespective of thickness with effect from 01.01.2019 under Environment (Protection) Act, 1986.
30. The project proponent & the industries to be in-housed shall ensure proper arrangement & utilization of recycled water.
31. The project proponent & the industries to be in-housed shall ensure that all trees & biodiversity listed in EIA report to be protected within the premises.
32. The project proponent & the industries to be in-housed shall ensure that the buildings should not cause any damage to water environment, air quality and should be carbon neutral building.
33. The project proponent & the industries to be in-housed shall ensure almost safety for the existing biodiversity, trees, flora & fauna shall not disturb under any circumstances.
34. The project proponent & the industries to be in-housed shall ensure that the all activities of EMP shall be completed before obtaining CTO from TNPCB.
35. The project proponent & the Industries to be in-housed shall ensure that the activities undertaken should not result in carbon emission, and temperature rise, in the area.
36. The project proponent & the industries to be in-housed shall ensure that the buildings and activities should not result in Environmental damages, nor result in temperature rise.
37. The project proponent & the industries to be in-housed shall provide and ensure the green belt plan is implemented as indicated in EMP. Also, the proponent shall explore possibilities to provide sufficient grass lawns.

  
**MEMBER SECRETARY**  
**SEIAA-TN**

38. The project proponent & the industries to be in-housed shall ensure to provide the emergency exit in the buildings.
39. The project proponent & the industries to be in-housed shall ensure to provide elevator as per rules CMDA/DTCP.
40. The proponent & the industries to be in-housed shall ensure to provide adequate capacity of DG set (standby) for the proposed STP so as ensure continues and efficient operation.
41. The proponent & the industries to be in-housed shall adhere to the provision and norms regard to fire safety prescribed by competent authority.
42. The project proponent & the industries to be in-housed shall adhere to storm water management plan as committed.

Environmental Clearance along with the conditions containing four parts namely

Part - A –Common conditions applicable for Pre-construction, Construction and Operational Phases

Part - B –Specific Conditions – Pre construction phase

Part - C – Specific Conditions – Construction phase

Part - D – Specific Conditions – Operational Phase/Post constructional Phase / Entire life of the project.

**Validity:**

**The SEIAA hereby accords Environmental Clearance to the above project under the provisions of EIA Notification dated 14<sup>th</sup> September, 2006 as amended, with validity for Seven years from the date of issue of EC, subject to the compliance of the terms and conditions stipulated below:**

**Part - A – Common conditions applicable for Pre-construction, Construction and Operational Phases:**

1. Any appeal against this Environmental Clearance shall lie with the Hon'ble National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.
2. The construction of STP, ETP, Solid Waste Management facility, E-waste management facility, DG sets, etc., should be made in the earmarked area only. In any case, the location of these utilities should not be changed later on.
3. The Environmental safeguards contained in the application of the proponent /mentioned during the presentation before the State Level Environment Impact

Assessment Authority / State Level Expert Appraisal Committee should be implemented in the letter and spirit.

4. All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire and Rescue Services Department, Civil Aviation Department, Forest Conservation Act, 1980 and Wild Life (Protection) Act, 1972, State / Central Ground Water Authority, Coastal Regulatory Zone Authority, other statutory and other authorities as applicable to the project shall be obtained by project proponent from the concerned competent authorities.
5. The SEIAA reserves the right to add additional safeguard measures subsequently, if non-compliance of any of the EC conditions is found and to take action, including revoking of this Environmental Clearance as the case may be.
6. A proper record showing compliance of all the conditions of Environmental Clearance shall be maintained and made available at all the times.
7. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company. The status of compliance of environmental clearance conditions and shall also be sent to the Regional Office of the Ministry of Environment and Forests, Chennai by e-mail.
8. The Regional Office of the Ministry located at Chennai shall monitor compliance of the stipulated conditions. The project authorities should extend full cooperation to the officer (s) of the Regional Office by furnishing the requisite data / information / monitoring reports.
9. "Consent for Establishment" shall be obtained from the Tamil Nadu Pollution Control Board and a copy shall be submitted to the SEIAA, Tamil Nadu.
10. In the case of any change(s) in the scope of the project, a fresh appraisal by the SEAC/SEIAA shall be obtained before implementation.
11. The conditions will be enforced inter-alia, under the provisions of the Water (Prevention & Control of Pollution) Act, 1974, the Air (Prevention & Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986, the Public Liability Insurance Act, 1991, along with their amendments, draft Minor Mineral Conservation & Development Rules, 2010 framed under MMDR Act 1957, National Commission for protection of Child Right Rules, 2006 and rules made there under and also any other orders passed by the Hon'ble Supreme Court of India/Hon'ble High Court of


  
**MEMBER SECRETARY**  
**SEIAA-TN**



Madras and any other Courts of Law, including the Hon'ble National Green Tribunal relating to the subject matter.

12. The Environmental Clearance shall not be cited for relaxing the other applicable rules to this project.
13. Failure to comply with any of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of the Environment (Protection) Act, 1986.
14. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, Chennai, the respective Zonal Office of CPCB, Bengaluru and the TNPCB. The criteria pollutant levels namely; PM<sub>10</sub>, PM<sub>2.5</sub>, SO<sub>2</sub>, NO<sub>x</sub> (ambient levels as well as stack emissions) or critical sectoral parameters, indicated for the project shall be monitored.
15. The SEIAA, TN may cancel the Environmental Clearance granted to this project under the provisions of EIA Notification, 2006, if, at any stage of the validity of this environmental clearance, if it is found or if it comes to the knowledge of this SEIAA, TN that the project proponent has deliberately concealed and/or submitted false or misleading information or inadequate data for obtaining the Environmental Clearance.
16. The Environmental Clearance does not imply that the other statutory / administrative clearances shall be granted to the project by the concerned authorities. Such authorities would be considering the project on merits and be taking decisions independently of the Environmental Clearance.
17. The SEIAA, TN may alter/modify the above conditions or stipulate any further condition in the interest of environment protection, even during the subsequent period.
18. The Environmental Clearance does not absolve the applicant/proponent of his obligation/requirement to obtain other statutory and administrative clearances from other statutory and administrative authorities.
19. Where the trees need to be cut, compensation plantation in the ratio of 1:10 (i.e. planting of 10 trees for every one tree that is cut) should be done with the obligation to continue maintenance.

20. A separate environmental management cell with suitable qualified personnel should be set-up under the control of a Senior Executive who will report directly to the Head of the Organization and the shortfall shall be strictly reviewed and addressed.
21. The EMP cost shall be deposited in a nationalized bank by opening separate account and the head wise expenses statement shall be submitted to TNPCB with a copy to SEIAA annually.
22. The Project Proponent has to provide adequate number of rain water harvesting pits to recover and reuse the rain water during rainy days as committed.
23. The project activity should not cause any disturbance & deterioration of the local bio diversity.
24. The project activity should not impact the water bodies. A detailed inventory of the water bodies and forest should be evaluated and fact reported to the Forest Department & PWD for monitoring.
25. All the assessed flora & fauna should be conserved and protected.
26. The proponent should strictly comply with, Tamil Nadu Government Order (Ms) No.84 Environment and forests (EC.2) Department dated 25.06.2018 regarding ban on one time use and throwaway plastics irrespective of thickness with effect from 01.01.2019 under Environment (Protection) Act, 1986.
27. Necessary permission shall be obtained from the competent authority for the drawl / outsourcing of fresh water before obtaining consent from TNPCB.
28. The proponent shall appoint an Environmental Engineer with necessary qualification for the operation and maintenance of STP (Sewage Treatment Plant) and GWTP (grey water Treatment Plant)
29. The Proponent shall provide the dispenser for the disposal of Sanitary Napkins.
30. All the mitigation measures committed by the proponent for the flood management, Solid waste disposal, Sewage treatment & disposal etc., shall be followed strictly.
31. No waste of any type to be disposed of in any watercourse including drains, canals and the surrounding environment.
32. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided.
33. The safety measures proposed in the report should be strictly followed.
34. The project proponent shall carryout CER activity as committed as per MoEF & CC O.M F.No.22-65/2017-IA.III dated: 30.09.2020 & 20.10.2020 before obtaining CTO from TNPCB.

  
**MEMBER SECRETARY**  
**SEIAA-TN**

**Part - B – Specific Conditions – Pre construction phase:**

1. **The project authorities should advertise with basic details at least in two local newspapers widely circulated, one of which shall be in the vernacular language of the locality concerned, within 7 days of the issue of clearance. The press releases also mention that a copy of the clearance letter is available with the State Pollution Control Board and also at website of SEIAA, TN. The copy of the press release should be forwarded to the Regional Office of the Ministry of Environment and Forests located at Chennai and SEIAA-TN.**
2. In the case of any change(s) in the scope of the project, a fresh appraisal by the SEAC/SEIAA shall be obtained before implementation.
3. **A copy of the clearance letter shall be sent by the proponent to the Local Body. The clearance letter shall also be put on the website of the Proponent.**
4. The approval of the competent authority shall be obtained for structural safety of the buildings during earthquake, adequacy of firefighting equipments, etc. as per National Building Code including protection measures from lightning etc. before commencement of the work.
5. All required sanitary and hygienic measures for the workers should be in place before starting construction activities and they have to be maintained throughout the construction phase.
6. Design of buildings should be in conformity with the Seismic Zone Classifications.
7. The Construction of the structures should be undertaken as per the plans approved by the concerned local authorities/local administration.
8. No construction activity of any kind shall be taken up in the OSR area.
9. Consent of the local body concerned should be obtained for using the treated sewage in the OSR area for gardening purpose. The quality of treated sewage shall satisfy the bathing quality prescribed by the CPCB.
10. The height and coverage of the constructions shall be in accordance with the existing FSI/FAR norms as per Coastal Regulation Zone Notification, 2011.
11. The Project Proponent shall provide car parking exclusively for the visiting guest in the proposed residential apartments as per CMDA norms.
12. The project proponent shall ensure the entry of basement shall be above maximum flood level.
13. The proponent shall prepare completion plans showing Separate pipelines marked with different colours with the following details

- i. Location of STP, compost system, underground sewer line.
  - ii. Pipe Line conveying the treated effluent for green belt development.
  - iii. Pipe Line conveying the treated effluent for toilet flushing
  - iv. Water supply pipeline
  - v. Gas supply pipe line, if proposed
  - vi. Telephone cable
  - vii. Power cable
  - viii. Storm water drains, and
  - ix. Rain water harvesting system, etc. and it shall be made available to the owners
14. A First Aid Room shall be provided in the project site during the entire construction and operation phases of the project.
15. The present land use surrounding the project site shall not be disturbed at any point of time.
16. The green belt area shall be planted with indigenous native trees.
17. Natural vegetation listed particularly the trees shall not be removed during the construction/operation phase. In case any trees are likely to be disturbed, shall be replanted.
18. During the construction and operation phase, there should be no disturbance to the aquatic eco-system within and outside the area.
19. The Provisions of Forest conservation Act 1980, Wild Life Protection Act 1972 & Bio diversity Act 2002 should not be violated.
20. There should be Firefighting plan and all required safety plan.
21. Regular fire drills should be held to create awareness among owners/ residents.

**Part - C - Specific Conditions – Construction phase:**

**1. Construction Schedule:**

- i) The Project proponent shall have to furnish the probable date of commissioning of the project supported with necessary bar charts to SEIAA-TN.

**2. Labour Welfare:**

- i) All the laborers to be engaged for construction should be screened for health and adequately treated before and during their employment on the work at the site.

  
**MEMBER SECRETARY**  
**SEIAA-TN**

- ii) Personnel working in dusty areas should wear protective respiratory devices and they should also be provided with adequate training and information on safety and health aspects. Occupational health surveillance program of the workers should be undertaken periodically to observe any contradictions due to exposure to dust and take corrective measures, if needed.
- iii) Periodical medical examination of the workers engaged in the project shall be carried out and records maintained. For the purpose, schedule of health examination of the workers should be drawn and followed accordingly. The workers shall be provided with personnel protective measures such as masks, gloves, boots etc.

### **3. Water Supply:**

- i) The entire water requirement during construction phase may be met from private tankers
- ii) Provision shall be made for the housing labour within the site with all necessary infrastructures and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, crèche etc. The housing may be in the form of temporary structures to be removed after the completion of the project.
- iii) Adequate drinking water and sanitary facilities should be provided for construction workers at the site. The treatment and disposal of waste water shall be through dispersion trench after treatment through septic tank. The MSW generated shall be disposed through Local Body and the identified dumpsite only.
- iv) Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices prevalent.
- v) Fixtures for showers, toilet flushing and drinking water should be of low flow type by adopting the use of aerators / pressure reducing devices / sensor based control.

### **4. Solid Waste Management:**

- i) In the solid waste management plan, the STP sludge management plan for direct use as manure for gardens is not acceptable; it must be co-composted with biodegradables.

- ii) Hazardous waste such as batteries, small electronics, CFL bulbs, expired medicines and used cleaning solvent bottles should be segregated at source, collected once in a month from residences and disposed as per the SWM Rules 2016.
- iii) Domestic solid wastes to be regularly collected in bins or waste handling receptacles and disposed as per the solid waste management rules 2016.
- iv) No waste of any type to be disposed of in any watercourse including drains, canals and the surrounding environment.
- v) E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016 and subsequent amendment.

**5. Top Soil Management:**

- i) All the top soil excavated during construction activities should be stored for use in horticulture/ landscape development within the project site.

**6. Construction Debris disposal:**

- i) Disposal of construction debris during construction phase should not create any adverse effect on the neighboring communities and be disposed off only in approved sites, with the approval of Competent Authority with necessary precautions for general safety and health aspects of the people. The construction and demolition waste shall be managed as per Construction & Demolition Waste Management Rules, 2016.
- ii) Construction spoils, including bituminous materials and other hazardous materials, must not be allowed to contaminate watercourses. The dump sites for such materials must be secured so that they should not leach into the adjacent land/ lake/ stream etc.

**7. Diesel Generator sets:**

- i) Low Sulphur Diesel shall be used for operating diesel generator sets to be used during construction phase. The air and noise emission shall conform to the standards prescribed in the Rules under the Environment (Protection) Act, 1986, and the Rules framed thereon.
- ii) The diesel required for operating stand by DG sets shall be stored in barrels fulfilling the safety norms and if required, clearance from Chief Controller of Explosives shall be taken.

  
**MEMBER SECRETARY**  
**SEIAA-TN**

- iii) The acoustic enclosures shall be installed at all noise generating equipments such as DG sets, air conditioning systems, cooling water tower etc.

**8. Air & Noise Pollution Control:**

- i) Vehicles hired for bringing construction materials to the site should be in good condition and should conform to air and noise emission standards, prescribed by TNPCB/CPCB. The vehicles should be operated only during non-peak hours.
- ii) Ambient air and noise levels should conform to residential standards prescribed by the TNPCB, both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during the construction phase. The pollution abatement measures shall be strictly implemented.
- iii) Traffic congestion near the entry and exit points from the roads adjoining the proposed project site shall be avoided. Parking shall be fully internalized and no public space should be utilized. Parking plan to be as per CMDA norms. The traffic department shall be consulted and any cost effective traffic regulative facility shall be met before commissioning.
- iv) The buildings should have adequate distance between them to allow free movement of fresh air and passage of natural light, air and ventilation.
- v) The project proponent should ensure that adequate Air Pollution Control measures shall be provided from buses and other vehicles, which will be entering the bus terminal. Further, water sprinkling system shall be provided and same shall be used at regular interval to control the dust emission within the project site.

**9. Building material:**

- i) Fly-ash blocks should be used as building material in the construction as per the provision of Fly ash Notification of September, 1999 and amended as on 27th August, 2003 and Notification No. S.O. 2807 (E) dated: 03.11.2009.
- ii) Ready-mix concrete shall alone be used in building construction and necessary cube-tests should be conducted to ascertain their quality.
- iii) Use of glass shall be reduced up to 40% to reduce the electricity consumption and load on air conditioning. If necessary, high quality double glass with special reflecting coating shall be used in windows.

**10. Storm Water Drainage:**

- i) Storm water management around the site and on site shall be established by following the guidelines laid down by the storm water manual.
- ii) Storm water management plan shall be obtained by engaging the services of Anna University/IIT.

**11. Energy Conservation Measures:**

- i) Roof should meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material, to fulfill the requirement.
- ii) Opaque wall should meet prescribed requirement as per Energy Conservation Building Code which is mandatory for all air conditioned spaces by use of appropriate thermal insulation material to fulfill the requirement.
- iii) All norms of Energy Conservation Building Code (ECBC) and National Building Code, 2005 as energy conservation have to be adopted Solar lights shall be provided for illumination of common areas.
- iv) Application of solar energy should be incorporated for illumination of common areas, lighting for gardens and street lighting. A hybrids system or fully solar system for a portion of the apartments shall be provided.
- v) A report on the energy conservation measures conforming to energy conservation norms prescribed by the Bureau of Energy Efficiency shall be prepared incorporating details about building materials & technology; R & U factors etc and submitted to the SEIAA in three month's time.
- vi) Energy conservation measures like installation of CFLs/TFLs for lighting the areas outside the building should be integral part of the project design and should be in place before project commissioning.

**12. Fire Safety:**

- i) Adequate fire protection equipments and rescue arrangements should be made as per the prescribed standards.
- ii) Proper and free approach road for fire-fighting vehicles upto the buildings and for rescue operations in the event of emergency shall be made.

**13. Green Belt Development:**

  
**MEMBER SECRETARY**  
**SEIAA-TN**



- i) The Project Proponent shall plant tree species with large potential for carbon capture in the proposed green belt area based on the recommendation of the Forest department well before the project is completed.
- ii) The proponent has to earmark the greenbelt area with dimension and GPS coordinates for the green belt area all along the boundary of the project site with at least 3 meter wide and the same shall be included in the layout out plan to be submitted for CMDA/DTCP approval.
- iii) The proponent shall develop the green belt as per the plan furnished and area earmarked for the greenbelt shall not be alter at any point of time for any other purpose.

#### **14. Sewage Treatment Plant:**

- i) The Sewage Treatment Plant (STP) installed should be certified by an independent expert/ reputed Academic institutions for its adequacy and a report in this regard should be submitted to the SEIAA, TN before the project is commissioned for operation. Explore the less power consuming systems viz baffle reactor, etc., for the treatment of sewage.
- ii) The Proponent shall install STP as furnished. Any alteration to satisfy the bathing quality shall be informed to SEIAA-TN.
- iii) The project proponent shall operate and maintain the Sewage treatment Plant and Effluent treatment plant effectively to meet out the standards prescribed by the CPCB.
- iv) The project proponent shall continuously operate and maintain the Sewage treatment plant and Effluent treatment plant to achieve the standards prescribed by the CPCB.
- v) The project proponent has to ensure the complete recycling of treated Sewage & Effluent water after achieving the standards prescribed by the CPCB.
- vi) The project proponent has to provide separate standby D.G set for the STP/GWTP for the continuous operation of the STP/GWTP in case of power failure.

#### **15. Rain Water Harvesting:**

- i) The proponent shall ensure that roof rain water collected from the covered roof of the buildings, etc shall be harvested so as to ensure the maximum beneficiation of rain water harvesting by constructing adequate sumps so that 100% of the harvested water shall be reused.

- ii) Rain water harvesting for surface run-off, as per plan submitted should be implemented. Before recharging the surface run off, pre-treatment with screens, settlers etc. must be done to remove suspended matter, oil and grease, etc.
- iii) The Project Proponent has to provide adequate number of rain water harvesting pits to recover and reuse the rain water during rainy days as committed.
- iv) The project activity should not cause any disturbance & deterioration of the local bio diversity.

**16. Building Safety:**

Lightning arrester shall be properly designed and installed at top of the building and where ever is necessary.

**Part – D - Specific Conditions – Operational Phase/Post constructional phase/Entire life of the project:**

1. There should be Firefighting plan and all required safety plan.
2. Regular fire drills should be held to create awareness among owners/ residents.
3. Hazardous waste such as batteries, small electronics, CFL bulbs, expired medicines and used cleaning solvent bottles should be segregated at source, collected once in a month from residences and disposed as per the SWM Rules 2016.
4. The building should not spoil the green views and aesthetics of surroundings and should provide enough clean air space.
5. Solar energy saving shall be increased to atleast 10% of total energy utilization.
6. The Project proponent has to spend the CER as committed in the affidavit. The above activity shall be carried out before obtaining CTO from TNPCB.
7. The EMP cost shall be deposited in a nationalized bank by opening separate account and the head wise expenses statement shall be submitted to TNPCB with a copy to SEIAA annually
8. The EMP cost shall be printed in the Brochure / Pamphlet for the preparation of the sale of the property and should also mention the component involved.
9. The Project proponent shall get due permission from the wetland Authority before the commencement of the work, if applicable.

  
**MEMBER SECRETARY**  
**SEIAA-TN**

10. The Project proponent should discuss with the wet land Authority, Tamil Nadu Forest Department, PWD and support lake restoration cum improvement, awareness and conservation programs.
11. The project activities should in no way disturb the manmade structures.
12. The Proponent shall do afforestation/ restoration programme contemplated to strengthen the open spaces shall preferably include native species along with the financial forecast for planting and maintenance for 5 years.
13. "Consent to Operate" should be obtained from the Tamil Nadu pollution Control Board before the start of the operation of the project and copy shall be submitted to the SEIAA-TN.
14. Raw water quality to be checked for portability and if necessary RO plant shall be provided.
15. The Proponent should be responsible for the maintenance of common facilities including greening, rain water harvesting, sewage treatment and disposal, solid waste disposal and environmental monitoring including terrace gardening for a period of 3 years. Within one year after handing over the flats to all allottees a viable society or an association among the allottees shall be formed to take responsibility of continuous maintenance of all facilities with required agreements for compliance of all conditions furnished in Environment Clearance (EC) order issued by the SEIAA-TN or the Proponent himself shall maintain all the above facilities for the entire period. The copy of MOU between the buyers Association and proponent shall be communicated to SEIAA-TN.
16. The ground water level and its quality should be monitored and recorded regularly in consultation with Ground Water Authority.
17. Treated effluent emanating from STP shall be recycled / reused to the maximum extent possible. The treated sewage shall conform to the norms and standards for bathing quality laid down by CPCB irrespective of any use. Necessary measures should be made to mitigate the odour and mosquito problem from STP.
18. The Proponent shall operate STP continuously by providing stand by DG set in case of power failure.
19. It is the sole responsibility of the proponent that the treated sewage water disposed for green belt development/ avenue plantation should not pollute the soil/ ground water/ adjacent canals/ lakes/ ponds, etc

20. Adequate measures should be taken to prevent odour emanating from solid waste processing plant and STP.
21. The e - waste generated should be collected and disposed to a nearby authorized e-waste centre as per E- waste (Management & Handling), Rules 2016 as amended.
22. Diesel power generating sets proposed as source of back-up power during operation phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets.
23. The noise level shall be maintained as per MoEF/CPCB/TNPCB guidelines/norms both during day and night time.
24. Spent oil from D.G sets should be stored in HDPE drums in an isolated covered facility and disposed as per the Hazardous & other Wastes (Management & Transboundary Movement) Rules 2016. Spent oil from D.G sets should be disposed off through registered recyclers.
25. The proponent is required to provide a house hold hazardous waste / E-waste collection and disposal mechanism.
26. The proponent shall ensure that storm water drain provided at the project site shall be maintained without choking or without causing stagnation and should also ensure that the storm water shall be properly disposed off in the natural drainage / channels without disrupting the adjacent public. Adequate harvesting of the storm water should also be ensured.
27. Used CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/rules of the regulatory authority to avoid mercury contamination.
28. Failure to comply with any of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of the Environment (Protection) Act, 1986.
29. The Environmental Clearance is issued based on the documents furnished by the project proponent. In case any documents found to be incorrect/not in order at a later date the Environmental Clearance issued to the project will be deemed to be revoked/ cancelled.

  
**MEMBER SECRETARY**  
**SEIAA-TN**

**Copy to:**

1. The Additional Chief Secretary to Government, Environment & Forests Dept,  
Govt. of Tamil Nadu, Fort St. George, Chennai - 9.
2. The Chairman, Central Pollution Control Board, Parivesh Bhavan,  
CBD Cum-Office Complex, East Arjun Nagar, New Delhi - 110032.
3. The Member Secretary, Tamil Nadu Pollution Control Board,  
76, Mount Salai, Guindy, Chennai-600 032.
4. The APCCF (C), Regional Office, Ministry of Environment & Forest (SZ),  
34, HEPC Building, 1<sup>st</sup> & 2<sup>nd</sup> Floor, Cathedral Garden Road, Nungambakkam,  
Chennai - 34.
5. Monitoring Cell, I A Division, Ministry of Environment & Forests,  
Paryavaran Bhavan, CGO Complex, New Delhi - 110003.
6. The Commissioner, Virudhunagar District.
7. Stock File.

**Signature Not Verified**

Digitally signed by Thiru.Deepak  
S.Bilgi  
Member Secretary  
Date: 7/31/2023 8:36:57 PM  
Page 37 of 37